

Comparative Cost Proposal

Dania Beach Pier - Electrical Works

Scope of Work (Parts and Labor)	R&R Electric	ATTAWAY Electric	Electrical Maintenance
Replace existing 400 amp with 600 amp 120/240v 3-phase meter can			
Install additional 200 amp 120/240v 3-phase service with 200 amp 42 circuit 3-phase panel for restaurant (located in kitchen). Both 600 and 200 amp mains to have shunt-trip breakers, with (1) trip switch located as fire dept. Requires.	\$ 24,680.00	\$ 32,600.00	\$ 31,250.00
Install 200 amp 120/240v 3-phase service to feed elevator, bait Shop, parking lot lighting and pier lighting. New mains and sub-panel to be installed in equipment room next to the elevator.	\$ 8,740.00	\$ 11,580.00	\$ 12,350.00
Tie in lighting from parking lot to new service.			
Relocate pier lighting to service.	\$ 18,800.00	\$ 23,850.00	\$ 24,000.00
Remove bait shop from restaurant, tie in to new service.			
Exclusion: Permit Fees			
TOTAL	\$ 52,220.00	\$ 68,030.00	\$ 67,600.00